Solar Street Lighting Wholesale Prices - 11/1/2011

	Model	Solar Panel	Solar panel Brackets	Controller	Lamp Source	Arm	Pole Height	Battery	Optional design	Whole Street Light Photo	FOB Factory With pole	FOB Factory Without pole
1	SSL-12VMLED-10W	monocrystalline 60Wp	included	12V 10A with PMW, timer and sensor control funciton	High Power LED 12V 10W 1000lumen	included	3~ 4meters height	12V 65Ah			$1,126.67	$796.67
2	SSL-12VMLED-20W	monocrystalline 120Wp	included	12V 15A with PMW, timer and sensor control funciton	High Power LED 12V 20W 2000lumen	included	4~ 5meters height	12V 75Ah			$1,443.33	$1,101.67
3	SSL-12VMLED-30W	monocrystalline 165Wp	included	12V 15A with PMW, timer and sensor control funciton	High Power LED 12V 30W 3000lumen	included	4~ 5meters height	12V 100Ah			$1,778.33	$1,420.00
4	SSL-12VPLED-30W	monocrystalline 165Wp	included	12V 15A with PMW, timer and sensor control funciton	High Power LED 12V 30W 3300	included	4~7meters height	12V 100Ah			$1,821.67	$1,463.33
5	SSL-12VPLED-36W	monocrystalline 190Wp	included	Controller 24V 20A with PMW, timer and sensor control funciton	High Power LED 12V 36W 3960lumen	included	6~7meters height	12V 150Ah			$2,226.67	$1,768.33
6	SSL-24VPLED-42W	monocrystalline 210Wp	included	Controller 24V 20A with PMW, timer and sensor control funciton	High Power LED 24V 42W 4620lumen	included	8~10meters height	12V 120Ah x 2			$2,755.00	$2,196.67
7	SSL-24VPLED-48W	monocrystalline 220Wp	included	Controller 24V 20A with PMW, timer and sensor control funciton	High Power LED 24V 48W 5280lumen	included	8~10meters height	12V 120Ah x 2			$2,815.00	$2,256.67
8	SSL-24VPLED-56W	monocrystalline 240Wp	included	Controller 24V 20A with PMW, timer and sensor control funciton	High Power LED 24V 56W 6160lumen	included	8~10meters height	12V 150Ah x 2			$3,038.33	$2,480.00
9	SSL-24VPLED-72W	monocrystalline 240Wp	included	Controller 24V 20A with PMW, timer and sensor control funciton	High Power LED 24V 72W 7920lumen	included	8~10meters height	12V 150Ah x 2			$3,068.33	$2,510.00

Terms: Prepaid

Lead Time: 4 weeks production time, plus shipping time

Freight: Quoted

Notes: LED Light, PV Module, Controller, Pole, Cable Wires, Breakers, Battery(s) and Battery Casing Included.

PV and battery are sized for dusk to dawn operation and 3 days of rainy / cloudy weather