



Solar Water Heater (SWH) Installed Systems - Passive

Gallons:	20	30	40	50
Collector:	3x8'	3x8'	4'x8'	4'x8'
Persons:	1 - 2	2 - 3	3 - 4	4 - 5

TCT / ProgressivTube

	PT20-3W	PT30-3W	PT40-3W	PT50-3W
Retail	\$3,630	\$4,126	\$4,675	\$4,929
Tax Credit 30%	-\$1,089	-\$1,238	-\$1,403	-\$1,479
FL Rebate	-\$500	-\$500	-\$500	-\$500
Net Price	\$2,041	\$2,388	\$2,773	\$2,950

Gallons:	60	80	100	120
Collector:	2 @ 3x8'	2 @ 4x8'	2 @ 4x8'	3 @ 4x8'
Persons:	4 - 6	6 - 8	8 - 10	9 - 12

TCT / ProgressivTube

	PT60-3W	PT80-3W	PT100-3W	PT120-3W
Retail	\$6,599	\$7,614	\$8,121	\$10,385
Tax Credit 30%	-\$1,980	-\$2,284	-\$2,436	-\$3,116
FL Rebate	-\$500	-\$500	-\$500	-\$500
Net Price	\$4,119	\$4,830	\$5,184	\$6,770

System includes feed/return 3/4" copper pipe/insulation run of 25ft, installed on one story shingle roof w/3ft tilt mounting hardware, w/3-Way package & AntiScald Mixing valve on existing tank located in unobstructed garage area.

Options

New Construction Rough-in (Milage Radius: 50 / 125 / 250)	\$ 71	\$ 177	\$ 354
Additional Feed/Return Pipe/Insulation per ft	\$ 4.77		
Additional Stories each	\$ 83		
Roof: Tile Retrofit / Tile New Construction / Metal	\$ 224	\$ 161	\$ 51
Deduction for Fixed Mount	\$ (33)		
Roof Slope over 6/12 / 8/12	\$ 167	\$ 273	
Crane Service (varies - call for quote)	\$ 665		
Existing Tank located inside main house or closet	\$ 83		
Replace existing 40Gal Tank*	\$ 542		
*Pre-drained Tank credit (when replacing tank)	\$ 20		
*Install tank on platform over 24"	\$ 42		
*Install tank pan	\$ 58		
*Extend tank pan drain line to outside	\$ 52		
*Install tank T&P line to outside	\$ 58		
Relocate or move shelves, boxes, appliances per hr	\$ 42		
Install tank on platform over 12"	\$ 42		
Connect/reconnect HRU, HWR, Ice Maker, additional H/C lines per hr	\$ 42		
Trenching - Dirt/Sandy Soil per ft (pipe extra)	\$ 2.50		
Trenching - Rocks/Roots/Coral per ft (pipe extra)	\$ 5.00		
Ground Mount w/concrete piers	\$ 500		
Anti-Scald Mixing Valve downgrade credit	\$ (144)		
2nd Tank Location - 3/4" Pex Pipe/Insulation Run per ft	\$ 3.33		
2nd Tank Location - Tank Removal & Pex Tie-in	\$ 58		
2nd Tank Location - Pex Tie-in w/1 3Way Valve	\$ 108		
2nd Tank Location - Pex Tie-in w/2 3Way Vavles	\$ 133		